331

OFFICE OF THE PRESIDENT, DISTRICT BOARD, KOLAR.

Notice dated 4th March 1930.

Notice is hereby given that sealed Tenders will be received up to 2 P.M. of 1st April 1930, at the Office of the President, District Board Office, for constructing a No. 2 Type Design School Building at Namagondlu, Goribidnur Taluk. An approximate estimate of quantities is given below. The work should be completed within four months from the date of acceptance of the Tender.

2. The plan, detailed estimate may be seen at the District Board Office between the hours of 11 A.M. and 5 P.M., on any working day.

3. Tenders should be submitted on the form prescribed for P. W. D. works. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash, as earnest money.

5. The final acceptance of any tender will rest with the President who does not bind himself to accept the lowest of any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor, who will be intimated thereof, will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT ESTIMATE.

Sl. No.	Items of work	Per	Quantity	Rate
				Rs.
1	Earthwork excavation for foundation	C.yds.	27	
2	Concrete in chunam mortar with burnt stone jelly ...	C.ft.	177	
3	Burnt stone in clay	,,	730	
4	Burnt brick in clay	,,	793	
5	Burnt stone slabs 5" thick (dressed)	Sq.ft.	138	
6	Teakwood work wrought and put up	C.ft.	59	
7	Woodoiling to woodwork	Sqr.	6·00	
8	Roofing with 1st class Mangalore tiles on teak reapers with nails, etc, complete.	,,	10·21	
9	Ridge tile set in mortar	R.ft.	83	
10	Chunam plastering	Sqr.	16·45	
11	Teakwood battened doors, complete	S.ft.	23	
12	Do windows do	,,	27	
13	Teakwood gateway, complete for class rooms ...	Sq.ft.	15	
14	Whitewashing two coats	Sqr.	16·45	
15	Gravel flooring including watering and consolidation ...	,,	5·1	
16	Chunam pointing	,,	2·02	
17	Tarring	Lump sum		
18	Construction of a compound wall with pillars ...	,,	,,	
19	Providing teak wood gate	,,	,,	
20	Site clearing and unforeseen	,,	,,	
21	Chacolate silicate painting three coats	Sq.ft.	115	
	Contingencies	...	...	
	Total	..	...	

N.B.—(Items are for one side of the structure of the Type design).

C. B. GOPALA RAO,
President.